

District of Columbia Clean Water Construction-State Revolving Fund (CWC-SRF) Site Summary

Schoolyard and Parkland Stormwater Retrofits			Grant Funding Year(s) FY2014	
RiverSmart Schools: J.O. Wilson Elementary			Lead Agency DOEE	
			Project Type Design/Construction	
Infrastructure Type Green	Project Category School/Recreational Facility Retrofit	Address 660 K Street NE		Status Complete
Design Start/End March 2016 – June 2016		Construction Start/End July 2016 – August 2016		
Objective Manage stormwater through the installation of green infrastructure.				
Outputs <ul style="list-style-type: none">Design and permitsRainwater harvesting system of three at-grade cisterns of 580 gallons capacity each735 ft² rain garden115 trees and shrubsOutdoor classroom and nature education areas				
Sewershed CSS	Watershed Anacostia River	Subwatershed Anacostia River		Ward 6
Outcomes				
Stormwater Treatment Volume	Contributing Drainage Area	Impervious Surface Removed	Trees Planted	Linear Stream Feet Restored
4,062 gallons	5,735 ft ²	n/a	17	n/a

Preconstruction



Construction



Completion

